

OCCUPATIONAL SAFETY AND HEALTH DEPARTMENT

CONDITIONS FOR SERVICE EXECUTION

Inspection and examination of the working equipment

The conditions which are necessary for the process of inspection and examination of the working equipment are:

- all the working equipment that is being inspected and examined must be in a working condition. All the working and protective elements must be present for the normal function in the work process must be installed
- During inspection and examination of the working equipment it is necessary that the client provides the appropriate technical documentation which he owns regarding the working equipment subjected to the inspection and examination (technical documentation of the manufacturer, instruction for safe work and equipment handling) which should be presented to the persons performing the inspection and examination of the working equipment.
- During inspection and examination of the working equipment the client has the obligation to appoint the person in charge whose duty is to guide the team performing the inspection and examination and also to give the necessary information regarding the equipment & the kind of electrical charge, the place of electrical charge, the way function during the work process, the present mechanical, technical and electrical protection on the equipment etc.) That person should be the production process manager (the boss, supervisor etc.) or someone from the maintenance service.

Also, it is necessary to provide the starting process of all the equipment and display the way the equipment subjected to inspection and examination works by the authorized person so that the full inspection and examination could be carried out. During inspection and examination of the lifts as the working equipment it is necessary to provide the presence of the authorized lift maintenance workers.

- For the working equipment which is being inspected with the load it is necessary that the client provides the certain testing load and that:
- for the crane inspection-test load (1,25 from the nominal crane capacity for the static inspection, or 1,10 from the nominal crane capacity for the dynamic inspection) for the newly installed cranes as well as nominal load and test load (1,10 from the nominal crane capacity) for every other inspection of the crane
- for the lift inspection-nominal load and test load (1,25 from the nominal lift capacity)
- for inspection of the lifting platform that uses mechanic drive, that uses built in platform or the basket, that is used for lifting and lowering the employees-test load

(1,30 from the platform nominal capacity for self-transferring platforms and 1,10 from the nominal platform capacity for all the other types of the lifting platforms)

- for inspection of the self-transferring vehicles, the use the mechanic drive, that is used for internal transport-towing, pushing (forest tractor, loco tractor etc.) or lifting, lowering and transferring the load (fork crane)-nominal load.